

QUOTATION NUMBER

Q-13287-4

QUOTATION DATE

March 12, 2024

QUOTATION PREPARED FOR

**Michael Addesso Marble & Granite World
129 West Penn Street
Norristown, Pennsylvania 19401
Attention: Chris Capodanno**

(610) 272-3372

DESCRIPTION

Mach 500

REGIONAL BUSINESS MANAGER

**Jody Bleiman
631-416-7272**

QUOTATION SUMMARY



Picture above depicts a Mach 500 system

System		Work Envelope	Price USD
Mach 500		4040 - 4 m x 4 m [13'-1" x 13'-1"]	\$ 414,450
Includes		Description	
1	Precision Z-Axis	Fully programmable servo-driven Z-Axis	
	Dynamic Waterjet®	- Automatic taper compensation to produce 2D parts with tight tolerances at higher speeds - Automatically adjusts for taper based on material type, speed, and desired edge finish	
	PASER® 4 cutting system	- New industry benchmark in cutting heads 408 kg [900 lb] abrasive delivery system	
2	FlowXpert Infinity™	- Roll-around control - FlowXpert Infinity™ software package	
3	HyperJet® 50 intensifier pump	50 hp, 6500 bar [94,000 psi] - Fastest cutting speeds with the lowest consumable and operating cost - Simplified maintenance to maximize uptime - Full enclosure with sound deadening and LED diagnostics	
4	CleanCut Material Support System	Heavy-duty steel construction	
5	Start-up services, installation, and training	Provided by Flow-certified technicians, included at no charge if installation is started within four (4) months of ship date (two seats of training also included to be used within one year of installation)	
6	Warranty	One (1) year warranty	
7	WaterjetConnect IQ™ by Flow®	- Identify system information for go-forward planning - Access data in real time from Flow - View information from anywhere and from any device	

Additional Items Included		Description		
8	Technology Package Includes Waterjet Connect iQ, Waterjet Connect, FlowXPERT Infinity and FlowCUT software	- Two seats of upgraded FlowXpert Infinity CAD software - Waterjet Connect iQ platform with machine data, alarms, and alerts - Two seats of FlowCUT Software		
9	UltraPierce™	Allows the user to automatically pierce holes in brittle and composite materials without breakage or delamination test		
10	Final Filter System	Designed to provide an additional filtration step prior to discharging to the sewer		
11	Laser Edge Finder	Allows operator to precisely position waterjet at an exact position on the work piece being cut		
12	Low-profile fixture clamps	Low-profile design provides greater mobility of the machine within the cutting environment		
Options		Description		Price USD
13	Dynamic XD®	- Automatic taper compensation to produce 2D and 3D parts with tight tolerances at higher speeds - Advanced beveling and 3D (5-Axis) capabilities		\$ 10,000
14	FlowCare for HyperJet 50	- Program covers 2,000 hours of pump runtime for up to two (2) years - Intensifier Exchange Program (for intensifier pumps only) - Flow performs all inspections, part replacement, and repair at the Flow Service/Rebuild Center - Includes all parts \$3,000 parts credit: Recommendations provided at installation by Flow Service Engineer based on estimated usage rates, application, water quality, and other factors - Key Consumables¹ provided at installation - Two (2) Preventive Onsite Service / Training Visits² 10% Discount on all maintenance kits for life of the program 10% Discount off Published Flow Service rates for life of program - Warranty extension for one additional year (warranty valid for 2 years or 4,000 hours starting on system ship date whichever comes first) - Program requires the customer to maintain basic water quality requirements		\$ 24,000

GENERAL COMMERCIAL TERMS

PRICES:	All prices quoted in United States Dollars
DELIVERY POINT – F.O.B., ORIGIN:	Freight charges: ☐ Flow Paid ☐ Customer Arranged ☒ Prepaid and Bill (additional administrative fee included) - XY from Vernon, CA (unless otherwise specified) - Pump and ancillary equipment from Baxter Springs, KS - Garnet locations to be determined (if applicable)
ESTIMATED SHIPMENT:	8 – 14 weeks after receipt of order and approval of credit <i>Subject to prior sale</i>
TITLE PASSAGE:	Origin
PAYMENT TERMS:	30% with Purchase Order 60% net 7 days after shipment or 14 days prior to installation start, whichever comes first 10% net 30 days after shipment This transaction and all of its terms and conditions are subject to final credit approval.
LEASE OPTIONS:	A variety of equipment lease plans are available upon credit approval. Please contact your Regional Sales Manager for details.

NOTES:

- The prices quoted herein EXCLUDE the following:
 - Local, state, and federal taxes, permits, and fees
 - Freight from Flow plants and suppliers to customer's location, unless otherwise specified
 - Customs clearance, including duties and fees
- Unless otherwise specifically stated in this quotation, the balance of the purchase price, together with any other related amounts, shall become immediately due and payable at the time the equipment included in this quotation, or any portion of it, is placed in service or used in any way other than in connection with its installation or testing.

Unless otherwise stated, pricing is valid for 30 days and may be modified or withdrawn by Seller prior to any acceptance. Prices F.O.B. KENT, WASHINGTON USA unless otherwise noted.

OFFERED by Flow International Corporation (Seller):	ACCEPTED by Buyer:
By:	Company:
Title: Regional Manager	By:
Date:	Date:

NOTICE: Sale of any product or services covered by this quotation is conditioned upon the terms contained herein (including those on the attached Conditions of Sale form). Any additional or different terms proposed by Buyer are objected to and will not be binding upon Seller unless specifically assented to in writing by the Seller.

TECHNICAL SPECIFICATIONS

1 Mach 500 Waterjet System

Mach 500 is the industry's most robust waterjet solution, unmatched in technology and design. Mach 500 provides accuracy, quickness, and speed, unlike any other waterjet. Cut more parts with unequalled exactness, elevating your production and performance levels.

Highlights include:

- The Mach 500 is built using modern architecture and combined with state-of-the art features like Dynamic XD and Compass (the most accurate contour following system for waterjet)
- Leading industry drives, motors, and electrical system coupled with Flow's ultrahigh-pressure technology
- All machine components controlled by convenient roll-around operating console that easily spans the entire work envelope
- Environmental protection package is comprised of heavy-duty collapsing bellows to protect base and bridge rail systems from the harsh waterjet environment
- The Y-Axis and the vertical Z-Axis utilize 360° wraparound bellows for true sealed protection. The X-Axis base also utilizes bellows and double shielding to provide complete environmental protection
- Laser calibrated at factory and dynamically ball bar tested at customer facility to ensure accuracy standards are validated
- Major welds are thermal stress relieved to ensure tight tolerances

Industry Standards

Flow prides itself with manufacturing safe products, designing the Mach waterjet series to the highest international electrical and safety standards for industrial machinery. At a minimum, the electrical design of the product line adheres to the following standards:
NFPA 70 (National Electric Code) controllers

Machine Specifications

Travel	
XY-Axis travel	4 m x 4 m [13'-1" x 13'-1"]
Z-Axis travel (standard)	305 mm [12 in.]
Speed Ranges	
Rapid traverse maximum	17.78 m/min [700 in./min]
Accuracy	
Linear straightness accuracy	± .0381 mm/m [± .0015 in./3 ft]
Repeatability	± .025 mm [± .001 in.]
Ballbar Circularity	± .0635 mm [± .0025 in.]
Acceleration	.1G

Dynamic Waterjet®

Flow applied its years of dedication to waterjet technology to develop the world's most advanced waterjet system—Dynamic Waterjet with Active Tolerance Control®. A machine equipped with Dynamic Waterjet provides cutting performances that were previously unobtainable. Get Dynamically Superior Parts—the most accurate, fastest, and comprehensive waterjet machine ever designed.

Dynamic Waterjet represents the single greatest improvement in abrasive waterjet cutting—ever. Flow has overcome what were commonly accepted limits of the waterjet process. Now it is possible to produce high tolerance parts at high cutting speeds. The taper imparted on parts by conventional waterjets is virtually eliminated. Parts with precise corner geometry are easily produced. For precision cutting, parts can be produced up to three times faster than on conventional waterjet systems, with virtually zero taper.

Dynamic Waterjet combines innovative kinematics with highly developed mathematical models and easy to use, intelligent software. Using Flow's revolutionary SmartStream™ technology to predict stream behavior during the cutting process, an operator can begin producing perfect parts with no specialized training. By simply entering the type of material, its thickness, and the desired edge finish, Flow's SmartStream technology calculates and precisely controls all the movements of the cutting head.

Features include:

- Rapid lift and drop is accomplished by precision servo drive
- Position feedback provides closed-loop control of the Z-Axis
- Underwater or above water operation
- 305 mm [12 in.] vertical travel
- Easy access cover protects critical precision components

PASER® 4 Cutting System


Building upon the success of the highest performing, most popular cutting heads in the waterjet industry, Flow engineers developed exclusive technology resulting in superior performance only available with Flow waterjet systems. Flow's newly designed PASER 4 cutting head establishes a new industry benchmark by featuring the greatest cutting speed coupled with the lowest operating cost.

PASER 4 Cutting Head

The cutting head accelerates the abrasive into the high-velocity waterjet to generate a high-energy abrasivejet cutting stream capable of cutting virtually any material.

The PASER 4 cutting head features:

- Orifice design increases component life 3–6 times over earlier generations and competing cutting heads



- On/Off valve allows for longer lasting components and higher reliability, decreasing maintenance required and increasing up time
- Increased productivity—longer-lasting parts means more runtime between maintenance intervals, lower inventory carrying costs and lower operating costs
- Orifice and mixing tube alignment is optimized by using tapered surfaces and an exclusive precision collet that automatically aligns all critical components
- PASER 4 features a 101 mm [4 in.] long mixing tube, which allows for a significant increase in life and reduction of taper over other cutting systems

PASER 4 Meeting Valve

Flow's PASER 4 metering valve eliminates abrasive clogging and surging for more consistent performance. The design ensures that the abrasive remains dry in particularly wet cutting environments. The new PASER 4 metering system delivers the precise amount of abrasive required by the PASER 4 cutting head in order to ensure maximum cut speed and efficiency.

PASER 4 Plumbing Package

The evolution of high-pressure plumbing led to a simple yet effective design for the high-pressure whip package. No swivels are needed, eliminating maintenance and line loss. The inherent flexibility of the long steel tubing provides all the necessary degrees of freedom that a moving cutting head requires. Plumbing package includes high pressure gauge, high-pressure whip, and plumbing support column.

PASER 4 Start-Up Kit

The PASER 4 cutting head comes with a standard start-up kit designed to get you up and running for the purpose of training and familiarization.

PASER CF900 Abrasive Delivery System

The PASER CF900 Abrasive Bulk Transfer System (ABT) is designed for the continual transport of abrasive materials. The system continuously monitors the corresponding filling level. A Programmable Logic Controller (PLC) processes electrical monitoring signals. A warning lamp and an audible warning indicator, located on the control cabinet, provide visual and audio feedback of the filling level.

- 900 lb capacity
- Position feedback provides closed-loop control of the Z-Axis
- Dual stage hopper allows continuous operation
- Audible and visual alarms for warning and shutdown



2 FlowCUT PC-Based Controller with FlowXpert™ Infinity software

Flow's PC-based controller with FlowCUT is the most advanced, state-of-the-art machine tool control system in the waterjet industry. This Simple Yet Powerful software suite is designed to be easy to use by operators of all skill levels. Using our unmatched experience as the inventors of abrasive waterjet, we have created the most extensive material library in the industry, featuring well over 100 lab-tested materials. FlowXpert, featuring SmartStream™ technology, understands precisely how the material and its thickness will affect stream behavior and takes all the guesswork out of making a perfect part the first time.

Once your geometry is chosen, FlowCUT applies Flow's exclusive SmartStream™ technology to optimize cutting speeds based on a variety of user- input parameters such as desired edge finish, material thickness, and material.

Hardware and PC

The PC hardware includes:

- Roll-around control with touch screen control console
- 381 mm [15 in.] color monitor, keyboard, mouse, and USB port

Features include:

- Exclusive SmartStream™ technology turns any novice operator into a professional
- Automatic and full control of the complete waterjet system directly from the control
- Simple and logical interface puts the operator in control
- Diagnostic screen allows easy system troubleshooting
- User-friendly, icon-based menu structure
- Easy, quick, surface quality specification
- Part preview displays and one click Dry Run option to test part programs
- Ability to pierce all holes first at low pressure, then cut at high pressure for use during special piercing operations of brittle materials
- Plate alignment function to compensate for plate rotation, angle or skew
- Array nesting with adjustable gap between parts
- Automatic part time estimation
- SmartStream™ cutting models assure high-quality finished parts
- Displays real-time tool location, including both machine home and floating user home
- Automatic cost per part generation based on user-defined parameters
- Warning and shutdown sensors are integrated directly into the control for easy troubleshooting
- Ability to set multiple user home positions
- Ability to generate customizable work order sheet
- Powerful, custom macro functions available for special applications
- Dynamically switch between languages while running program so multiple users can work in the language of their choice without having to shut the program down
- Restart a cut from any point on the path or nest
- 0 to 125% feedrate override

FlowXpert Infinity Software Package

Revolutionary, state-of-the-art waterjet software encompassing all 2D & 3D cutting – comprehensive, powerful, easy to use solution, capable of powering your entire shop.



Highlights include:

- Full CAD Package offers functionality to both 3D and 2D models
- Optimized waterjet software out of the gate, which dramatically reduces design time
- The only software in the industry where the OEM provides a fully integrated non-third party software that allows the customer to go from design to production in full 3D
- Onboard expert intelligence optimizes your waterjet cut with intuitive solutions
- Increase productivity with features such as AutoPath, Lead-in/Lead-out generation, and Multi-part array's
- Power your whole shop, not just your waterjet with one solution

3 HyperJet® 50 hp Intensifier Pump

Flow intensifier pumps set the industry standard for waterjet and abrasive waterjet cutting applications. Pressure = Productivity.



Highlights include:

- 6500 bar [94,000 psi] maximum generated pressure and 6000 bar [87,000 psi] operating pressure
- The integrated pump is located within the machine frame with easy access for maintenance
- Durable pump design with full intelligent controls, monitoring, and communication ability
- Extremely quiet operation
- Ergonomic handle-integrated status light combined with a bright interior work light designed for convenience
- Additional control panel at pump for easy maintenance and diagnostics
- Innovative seal carrier design for maximum performance and easy maintenance
- Motor starter and electrical panel integrated on heavy duty pump frame
- Electrically-shifted 6500 bar [94,000 psi] rated HyperPressure™ intensifier with ceramic plungers to minimize component wear
- 50 hp TEFC electric motor

- Solid-state soft starter motor control
- 1.1 L [67.1 in.³] maintenance-free attenuator to maintain constant output pressure
- Water booster and filtration system to ensure quality and constant water pressure; a two-stage filter bank filters water of particulate matter to 0.5 micron

Flow designed the HyperJet 6500 bar [94,000 psi] rated integrated pump to be easy to operate and maintain. All pump controls are found at the operator station. The pressure settings and pump on/off are conveniently displayed at the operator station. The integrated diagnostic screen displays the status of shutdown sensors for low hydraulic oil level, high hydraulic oil temperature, and low inlet water pressure. Also displayed are warning sensors for high hydraulic oil temperature, low inlet water pressure, high bleed-down, and check valve temperature.

Additional features include:

- Full electronic pressure control means the pressure setting and control is integrated into the Flow controller which greatly enhances operator convenience
- Dual pressure control - provides the user with a simple way to switch between two output water pressures. It is designed for applications where a low-pressure pierce is necessary before a higher pressure cutting operation
- Digital pressure transducer and display make it easy for operators to see their operating pressure reducing the possibility of damaged work materials due to incorrect pressure
- Cooling water flow control uses a thermostatically controlled valve to regulate cooling water flow while minimizing water usage
- Automatic high-pressure bleed-down valve to relieve system water pressure to 0 bar [0 psi] within 1 second of shutting down the pump
- When the pump is powered down or the emergency stop is activated, solenoid valves automatically shut off both the filtered water and pump cooling water. This option overrides automatic cooling water flow control and maximizes water savings

Industry Standards

In addition to exceptional performance and high reliability, safety is designed into all Flow products. This pump is designed for safe, reliable, continuous operation at 6000 bar [87,000 psi] in tough industrial cutting applications.

Pump Enclosure

The ultrahigh-pressure pump rests within an attractive enclosure that is visually and functionally integrated into the machine tool system. Features include:

- Air assisted lifting top
- Removable side panels for full maintenance accessibility

HyperJet Pressure Loading Tool

A hydraulic pressure loading tool allows for quick, accurate, and easy seal changes.

HyperJet Tool Kit

As with any high-performance machine, the HyperJet pump requires periodic maintenance and service. Flow created exclusive tools to ensure easy, consistent and reliable maintenance for all HyperJet components. The customized tool kit facilitates maintenance and consists of items such as girth and spanner wrenches and seal installation tools. In addition, you will receive medical alert cards for the system operators.



4 CleanCut Material Support System

More than just a catcher tank, Flow's CleanCut Material Support System incorporates a host of features that will provide tremendous benefits to your operator every day. Features include:

- Heavy-duty steel construction
- 992 mm [39.1 in.] work table height
- Replaceable slats installed in a curved configuration to increase load-bearing capability. The curve configuration reduces splash back when cutting square parts.
- 2438 kg/m² [500 lb/ft²] load rating
- Tooling clamp support platform

Water Level Control Module

Integrated with the CleanCut Material Support System, the water level control module enables water level control at the operator station. The ability to set the desired water level allows for underwater cutting, which virtually eliminates cutting noise and dramatically increases cleanliness.

5 Start-Up Services, Installation, and Training

Flow International Corporation (Flow) provides onsite start-up services, installation, and training to ensure a quick and seamless transition to maximum productivity (two free seats of training to be used within one year of installation and the machine installation must start within four months of the ship date). Start-up services and installation are included if customer fulfills the installation responsibilities noted below. Additionally, Flow will provide pre-installation instructions and the assistance of a Project Manager to help you prepare your site for the installation so it can proceed without delays. If additional time is required due to site readiness delays, Flow will bill the customer at standard technical service rates.

Start-Up Services

A qualified Field Service Engineer (FSE) will perform start-up services at the customer site following the customer's placement of the system in accordance with Flow's instructions and pre-installation package. Flow's FSE will review the pre-installation work to ensure that the electrical, plumbing, pneumatic, and other services are in accordance with Flow's recommendations.

With the assistance of a customer-provided technician, the FSE will assemble, level, and align the XY machine. The FSE will custom-form all high-pressure tubing to connect the pump to the X-Y machine. The customer-provided technician will bracket or mount tubing as required.

The FSE, with the assistance of the customer's electrician and plumber, performs the initial start-up of the system. Before commissioning the system for full operation, the FSE will flush the system and perform any necessary corrective measures.

Customer Installation Responsibilities

Listed below is a general overview of customer installation responsibilities.

- **Environment:** Recommended maximum ambient operating temperature is 40°C [105°F]
- **Equipment clearances:** To maximize the cutting area of your waterjet system, the machine requires a floor-to-ceiling clearance height of 4.7 m [15 ft-5 in.] for 60K pumps or 4.4 m [14 ft-4 in.] for 94K pumps. Local codes and regulations will determine actual required minimum clearance distance.
- **Electrical:** Perform all power connections in accordance with all local codes and Flow's pre-install package. Provide a true, uninterruptable earth-ground. For building voltage other than 440V–480V, a transformer may be required. (208V, 230V, and 575V services are available at additional cost)
- **Foundation:** To maintain accuracy, provide an adequate foundation to support the equipment. Flow recommends the floor be level to 20 mm [$\frac{3}{4}$ in.] over Mach 500 footprint and free of cracks or joints within the entire machine area.
- **Personnel & Scheduling:** Please provide a qualified technician to assist the Flow technician with the start-up and installation of the system. Schedule start-up services to coincide with the completion of your pre-installation responsibilities a minimum of three weeks prior to the desired arrival of the FSE. Please allow a minimum of one week between final delivery of the equipment and the arrival of the technician.
- **Plumbing:** Perform all air, water, and drain connections in accordance with all local codes and Flow's pre-install package
- **System arrival:** Provide onsite unloading and transport of equipment (requires 5000 kg [10,000 lb] capacity forklift with 2000 mm [84"] forks) from delivery truck to floor area where Mach 500 will be located. Uncrate and place equipment in its proper position per Flow's pre-install information. Please keep floor area where machine is located clear with unobstructed access to equipment.
- **Tools & Supplies:** Hammer drill for lagging system to floor and 2 m [7 ft] stepladder. Provide the proper oil and fill the pump reservoir with it. (HyPlex® pumps require Shell Morlina 100® oil or equivalent. Intensifier pumps require Shell Tellus® S2 M 46 hydraulic oil or equivalent.)

Training

Flow provides an instructor led three-day online system training class through Flow's training portal combined with one day of onsite familiarization training.

- **Three-day online system training:** Flow strongly recommends attending the online training prior to installation, as it will be required for operating the system. It includes operation/programming training on the X-Y machine and maintenance training for the high-pressure system for two people. Check schedule availability at least four (4) weeks prior to the desired training dates.

- *Onsite familiarization training:* Operators who previously attended Flow's online system training class will be reacquainted with their system and have the opportunity to apply their online training to operate it in a production capacity (approximately four hours). Maintenance technicians receive approximately four (4) hours of additional onsite maintenance familiarization, including an overview of the system. Please note that onsite familiarization training is not a substitute for Flow's three-day online system training class.

Notes:

The online operation/programming and onsite familiarization training require operators have a good working knowledge of personal computers and Windows® operating systems.

Inlet Water Test Kit

The test kit samples inlet water quality to determine if a water softener or other pre-treatment is required.

Professional Project Management

From purchase to installation, you will have a single point of contact to ensure an efficient system start-up. You will receive a thorough presentation of pre-install requirements and individualized project coordination, with personal attention and rapid response to special requirements.

6 One (1) Year Warranty

- This warranty term is one (1) year from the date of system shipment or 2000 hours, whichever comes first. It covers the following: equivalent parts and outbound ground freight, scheduled labor, and travel expenses. All other elements of the Limited Warranty apply.
- In order to qualify for this warranty period, at least one person within the customer's organization assigned to maintain the equipment must attend a free system maintenance training course prior to or within three (3) months of system installation. If training is not elected, a six (6) month warranty will apply.

7 WaterjetConnect IQ™ by Flow®


Access information about your system anytime, anywhere and from any connected device. Flow's 45 years of leadership in waterjet technology and innovation brings you Waterjet Connect – your unique, one-stop shop for accessing all things related to your waterjet system.



With WaterjetConnect™ you can:

- Proactively manage your maintenance and track trends in real time
- Order parts and view your order history
- Schedule training and access your service history
- Access waterjet videos and documents
- Easily add users
- Desktop, tablet, and phone compatible

With Waterjet Connect, more exciting features continue to get added regularly. As your business grows, so will the power of WaterjetConnect™, an exclusive benefit just for being a Flow customer.



ADDITIONAL ITEMS INCLUDED

8 Technology Package

This premium package ensures that your system will always be equipped with the latest technology long after your initial investment. This package contains the following features:

Package

- FlowXpert Infinity: The premier software in the industry and includes both full 2D and 3D drawing and part-pathing capability
- Upgraded Industrial PC: This high-performance pc is IP66 rated and comes with 24GB of ram
- Waterjet Connect iQ: Machine alarms, alerts, and data accessible anytime and anywhere
- Two (2) years of software upgrades and access to Waterjet Connect iQ IoT platform

FlowXPert Infinity

FlowXpert Infinity is the premier software in the industry and includes both full 2D and 3D modeling and part-pathing capability. More than just a software for your waterjet, FlowXpert Infinity is capable of powering your entire shop. FlowXpert is continually updated throughout the year with advanced features and the ability to read the most recent CAD files in most common formats.

FlowCUT Software

FlowCUT features a host of advanced features to maximize your productivity while minimizing your time. Using our unmatched experience as the inventors of abrasive waterjet, we have created the most extensive materials library in the industry, featuring well over 100 lab-tested materials. FlowCUT, featuring SmartStream™ technology, understands precisely how your material and its thickness will affect stream behavior and takes all the guesswork out of making a perfect part the first time.

Upgraded Industrial PC

This high-performance PC is IP66 rated, making it waterproof from a direct spray of water. Additionally, it is rated to safely operate at an ambient temperature of 50°C, far more than traditional PC's. The Intel chipset, high-powered graphics card, and abundant 24GB of RAM memory aren't just designed to run the FlowXpert Infinity and Waterjet Connect software of today, but tomorrow as well.

Waterjet Connect IQ

The technology package includes two-year access to Waterjet Connect iQ and is available via the Waterjet Connect portal. This can be accessed directly on the waterjet system controller in addition to any PC or mobile device. Waterjet Connect iQ features advanced IoT and system monitoring that can alert users to potential problems before they happen, helping to prevent downtime. Waterjet Connect iQ shows you exactly what you need to know to keep your machine running at optimal performance.

9 UltraPierce™

The UltraPierce vacuum assist allows the user to automatically pierce holes in brittle and composite materials without breakage or delamination. A vacuum created in the cutting head draws abrasive into the mixing chamber before turning on the high-pressure water. This eliminates top surface damage due to “water hammer.”



The system mounts to the nozzle body and is controlled from the PC. The vacuum assist includes 3 main features:

- Vacuum assist unit: Mounts to the cutting head and contains a small vacuum unit and pinch valve to seal the cutting head when the unit is not in use
- Solenoid control assembly: Mounted to the Z-Axis and contains the solenoid valve and logic to control the assist unit
- Abrasive containment (shop vac): Contains and stores the excess abrasive used by the system and prevents the discharge of abrasive dust into the work environment

10 Final Filter System

This system provides an additional filtration step prior to discharging to the sewer. Highlights of the Final Filter System include:

- 3-stage weir tank
- Filter pump with automatic controls
- Filter housing designed to hold two 500 mm [20 in.] long filter cartridges. System is supplied with two 50 micron filter cartridges (1 to 100 micron rated cartridges are available the nature of the waste stream will determine the most suitable filter rating)
- Indicator gauge to monitor filter condition
- Wired for 115 VAC, 1 phase, 60 Hz at 8 amps standard 3-prong male plug

Note: The customer should consult local regulations to determine exact discharge requirements.

11 Laser Edge Finder

The laser edge finder allows a waterjet operator to precisely position their Flow waterjet cutting nozzle at an exact position on the work piece being cut. The laser edge finder is used to jog around the work piece to mark chosen locations. FlowMaster or FlowXpert is used to quickly record these locations up to ten user-definable home positions can be programmed for the machine. The edge finder uses the locations to pinpoint the true edge of the material.


12 Low-profile fixture clamps

Low-profile clamps are adjustable to hold material from thin sheets to 38 mm [1.5 in.] thick. This low-profile design provides greater mobility of the machine within the cutting environment.

OPTIONS

13 Dynamic XD®

Dynamic XD introduces the first high-precision 3D cutting technology of its kind. Using a small articulated wrist, the original Dynamic Waterjet automatically tilts the waterjet cutting head in any direction up to 10° to eliminate stream lag and kerf taper errors—resulting in the tightest part tolerances and highest cutting speeds. That same core technology has been developed further with Dynamic XD, incorporating groundbreaking advantages with a standard 60° of articulation for bevel and 3D part production.



Up to 89° of articulation is available and is subject to additional terms and conditions acknowledging that constraints exist to successfully cut a part at 60° or more. To guarantee system performance, a test cut of your desired part must be done prior to purchase. Get *Dynamically Superior Parts* with Dynamic XD.

Features include:

- Rapid lift and drop is accomplished by precision servo drive
- Position feedback provides closed-loop control of the Z-Axis
- Underwater or above-water operation

- 305 mm [12 in.] vertical travel
- Zero tool length design allows jet to maintain correct position without having to move the X or Y Axis during multi-axis moves, resulting in a quicker, more accurate finished part
- Easy access cover protects critical precision components
- Laser-alignment using Flow's exclusive DynAlign™ System ensures ultimate precision
- Patented wrist design minimizes singularity moves when operating in 5- Axis mode, creating an optimized cut path and a more attractive finished part

Additional information regarding Dynamic XD:

- 89° of motion does not guarantee an effective 89° cutting angle. Additional taper compensation and compounded angles will often create the need for additional degrees of motion beyond the desired finished angle.
- Travel: X–Y travel may be reduced when cutting large angles facing away from the center of the catcher tank. Z travel may decrease if floor is significantly out of level.
- Equipment: 5-Axis waterjet cutting systems may require secondary safety systems for safe operation. These systems are specific to your installation. Flow offers standard solutions; please consult your Flow representative for assistance.
- *Personnel:* Safe operation of your system depends on proper installation and properly trained personnel. Flow offers training for your operators. Do not operate the equipment unless under the supervision of a certified technician.

Low-Profile Fixture Clamps

Low-profile clamps are adjustable to hold material from thin sheets to 38 mm [1.5 in.] thick. This low-profile design provides greater mobility of the machine within the cutting environment.

Laser Edge Finder

The laser edge finder allows a waterjet operator to precisely position their Flow waterjet cutting nozzle at an exact position on the work piece being cut. The laser edge finder is used to jog around the work piece to mark chosen locations. FlowXpert is used to quickly record these locations up to ten user-definable home positions can be programmed for the machine. The edge finder uses the locations to pinpoint the true edge of the material.

PASER® 4 Cutting System

Building upon the success of the highest performing, most popular cutting heads in the waterjet industry, Flow engineers developed exclusive technology resulting in superior performance only available with Flow waterjet systems. Flow's newly designed PASER 4 cutting head establishes a new industry benchmark by featuring the greatest cutting speed coupled with the lowest operating cost.

PASER 4 Cutting Head

The cutting head accelerates the abrasive into the high-velocity waterjet to generate a high-energy abrasivejet cutting stream capable of cutting virtually any material.



The PASER 4 cutting head features:

- Orifice design increases component life 3–6 times over earlier generations and competing cutting heads
- On/Off valve allows for longer lasting components and higher reliability, decreasing maintenance required and increasing up time
- Increased productivity—longer-lasting parts means more runtime between maintenance intervals, lower inventory carrying costs and lower operating costs
- Orifice and mixing tube alignment is optimized by using tapered surfaces and an exclusive precision collet that automatically aligns all critical components
- PASER 4 features a 101 mm [4 in.] long mixing tube, which allows for a significant increase in life and reduction of taper over other cutting systems

PASER 4 Meeting Valve

Flow's PASER 4 metering valve eliminates abrasive clogging and surging for more consistent performance. The design ensures that the abrasive remains dry in particularly wet cutting environments. The new PASER 4 metering system delivers the precise amount of abrasive required by the PASER 4 cutting head in order to ensure maximum cut speed and efficiency.

PASER 4 Plumbing Package

The evolution of high-pressure plumbing led to a simple yet effective design for the high-pressure whip package. No swivels are needed, eliminating maintenance and line loss. The inherent flexibility of the long steel tubing provides all the necessary degrees of freedom that a moving cutting head requires. Plumbing package includes high pressure gauge, high-pressure whip, and plumbing support column.

PASER 4 Start-Up Kit

The PASER 4 cutting head comes with a standard start-up kit designed to get you up and running for the purpose of training and familiarization.

14 FlowCare

Intensifier Maintenance

Intensifier exchange program for up to two (2) years, based on 2000 hours of operation. Flow assumes all costs for intensifier parts replacement, labor, and freight. Customer responsible for the onsite Intensifier Exchange**.

Consumables Package

Key consumables¹ and other items necessary for startup included. \$3,000 in parts credit applied to customer account. Post installation recommendation of on hand inventory of Genuine Flow Parts delivered by expert Flow Field Service Engineer based on application, expected run rate, and other considerations.

Warranty

One year / 2,000 hour warranty extension included.

Program covers 2,000 hours of pump runtime or up to 2 years from installation, whichever comes first.

- Program provides up to two (2) onsite visits² by a Flow technician throughout the program. Each visit should be scheduled at least three (3) weeks in advance, as they are preventive in nature and not to be used for emergency repair.
- Any additional services requested and provided by Flow outside of the above scope will be billable at 10% off Flow International's published Service Rates.
- Should there be any Warranty issues requiring an onsite visit, this will not count towards FlowCare.
- Program provides Key Consumables¹ package at installation of Flow Waterjet system.
- Program provides an additional \$3,000 parts credit applied to the Customer's account with Flow.
 - An expert Flow Field Service Engineer will recommend additional parts for customer's on hand inventory during the installation of Flow Waterjet System, based on application and other factors.
 - Parts credit may be consumed whenever and on whatever aftermarket items the Customer chooses.
 - This credit expires at end of the program, but can be applied to renewal.
- Customer is entitled to a Full PM inspection which includes a Ballbar Adjustment, Pump Diagnostics, and Hydraulic Oil change at a reduced rate (25% discount) at the expiration of the program.
 - Customer is responsible for providing the hydraulic oil and disposal container(s).
- Program provides up to two years or 2,000 hours' worth of intensifier exchanges with all repair, parts replacement, and shipping charges covered by Flow International. FlowCare begins at the completed installation date for new systems.
 - All active FlowCare customers receive a 10% discount on Flow International's published Service Rates.
 - Program requires inlet water flow rate, quality, and temperature analysis for eligibility. Unfavorable test results outside Flow International's specifications may require additional mitigation paths (chiller, water softener, etc) in order to consistently achieve predicted preventative maintenance schedule.
 - Failure to meet water specifications and causing premature failures may result in Customer being charged for freight, excessive rebuild costs, and even termination of the Program.
- Intensifiers on the program are serviced by certified Flow Technicians at the Flow Service Center:
Flow Service/Rebuild Center
635 West 12th Street
Baxter Springs, KS 66713
- Only Flow intensifiers enrolled in the FlowCare program can be returned to the Flow Service Center. Flow not responsible for return of any shipments or shipping costs associated with intensifiers not meeting these criteria.

- Damaged, tampered, or abused intensifiers may be subject to customer payment for the rebuild costs or replacement³ of a new intensifier.
- This is defined as directly tampering with or damaging the intensifier, operating when signs of failure are evident, or consistently operating with water quality and temperature outside of Flow's required tolerances causing irreparable damage to the intensifier.
- Program intensifiers that are clearly operated beyond the committed maintenance interval (determined by application and water quality results) are subject to pay for the rebuild or even replacement of that mistreated intensifier..
- Program termination occurs if Non-Flow parts are used on any part of the Flow Waterjet during the program.
- Customer not assured to receive the original intensifier(s) throughout the program.
- Only intensifiers on the program can be returned – Pay for full price intensifier if non-program serial number or intensifier is returned.
- Customer not assured to receive the same intensifier(s) throughout or at the end/expiration of the program.
- Every intensifier shipment from Flow contains one set of pump water filters, documentation, and o-ring (if needed).
- Prior to return shipment of “consumed” intensifier, all oil and water must be drained, and the intensifier plugged.
- Non-compliance may result in an Environmental fee of up to \$1,000.
- All intensifier freight to be paid by the customer.
 - Canadian customers to pay for intensifier freight, duties and taxes.
 - For shipped consumables, Flow to pay for shipping, customer to pay for duties and taxes.
- After receiving replacement intensifier, the Customer has two (2) calendar weeks to contact the FlowCare Project Management team (programs@flowcorp.com) to ensure the return of the “consumed” intensifier in the provided shipping container.
- Failure to comply will result in Customer paying freight of the shipment.
- If intensifier is not returned within 30 days of receipt of replacement intensifier, it will be considered purchased, and Customer is charged for missing intensifier³.

- Prior to return shipment, the Intensifier Return Form must be filled out in its entirety and placed in Flow provided shipping container with the intensifier. Exchanges/returns will not be accepted or processed until form is both filled out and submitted. Undocumented intensifiers are subject to the terms of Items 6, 7, and 13.
- In the unlikely event that an intensifier fails significantly premature to the committed service interval, Flow will ship a replacement unit with expedited shipping, free of charge.
- Customer is responsible for contacting the program coordinator or manager with updated program hours each month. Program hours can also be updated online through the Customer Portal.
- Program is non-transferable unless written consent from Flow International is supplied.
- ** An Intensifier Exchange involves manually removing an intensifier from the pump and replacing with another. This procedure is uncomplicated, takes about 20 minutes, and Flow will provide training during installation.
- ¹ Key Consumable quantities determined by application (abrasive v. water only).
 - Abrasive Applications: 5 Premium Mixing Tubes, two (2) Diamond Orifices, three (3) Blast Discs, three (3) Blast Shields, two (2) On/Off Valve Maintenance Kits, one (1) Collet, one (1) O-ring, two (2) Water Filters, one (1) Oil Filter, one (1) Oil Filter O-ring
 - Water Only Applications: five (5) Diamond Orifices, three (3) Blast Discs, three (3) Blast Shields, two (2) On/Off Valve Maintenance Kits, one (1) Collet, one (1) O-ring, two (2) Water Filters, one (1) Oil Filter, one (1) Oil Filter O-ring
- ² Each visits covers up to eight (8) hours of onsite service/training time, up to eight (8) hours of total travel time, and up to \$800 in expenses. Anything above these thresholds will be billed according to Flow published Service Rates.
- Replacement intensifier costs - ESL intensifier > **\$10,000**

TERMS AND CONDITIONS – APRIL 2018

The terms and conditions set forth herein, the express terms and conditions of the attached quotation, and the terms and conditions in the order acknowledgement or confirmation (if any) constitute the "Agreement" between Flow and the Buyer and supersede all prior correspondence, quotations, and other communications, either oral or written. These terms and conditions ("Terms") are intended to govern the sale of all waterjet cutting systems, surface preparation systems, pumps, as well as spare parts and consumables for such systems (the "Equipment"), and services where applicable.

1. LIMITED WARRANTY

a. Flow warrants the Equipment to be free from defects in workmanship and materials for the period specified on the quotation, except that spare parts shall be warranted for a 90 day period and electronic components for a 30 day period. This limited warranty does not cover normal wear and tear, consumable items including, but not limited to, seals, mixing tubes, filters, orifices, low and high-pressure plumbing and cylinders, or part failures caused by (i) accident or any act of God, (ii) abuse, or (iii) failure to maintain the Equipment in accordance with Flow technical specifications. Flow's liability is limited to repair or replacement of the Equipment and the determination regarding which of these is appropriate shall be at Flow's sole discretion. This warranty is conditioned upon (i) Flow being notified in writing by Buyer within one month after discovery of defects, (ii) At Flow's discretion, the return of defective Equipment to Flow (with RMA number assigned by Flow's customer service representative), with inbound transportation charge prepaid by Buyer, and (iii) Flow's examination of the Equipment and determination that such defects were not caused by negligence, misuse, improper maintenance, improper installation, accident or act of God, or unauthorized repair or alteration. Equipment or parts thereof furnished by Flow, but manufactured by others, shall carry the warranty that such product's manufacturer has conveyed to Flow, if any. The original warranty period of any Equipment that has been repaired or replaced by Flow shall not by virtue of such repair or replacement be extended. Warranty is void if non-Flow branded or certified or unauthorised parts are used.

b. Flow warrants that all products manufactured by Flow comprised in the Equipment and furnished to Buyer are delivered free of any rightful claim of any third party for infringement of any valid United States patent. If Buyer promptly notifies Flow, in writing, that it has received notice from a third party that the Equipment infringes a U.S. patent, and provides Flow with all authority, information and assistance that Flow deems reasonably necessary, Flow shall in its sole judgment defend or settle any suit or proceeding against Buyer, at Flow's expense, to the extent that it is based upon claim of infringement which is a breach of the foregoing warranty, and Flow shall pay all damages and costs awarded therein against Buyer due to such breach. In case the use of any such Equipment is held in such suit to constitute such an infringement and the use of such Equipment for its intended purpose is enjoined or restricted by way of a court-ordered injunction, Flow shall, at its expense and option, procure for Buyer the continued usage of said product or part, or replace same with a non-infringing product or part, or modify same so it becomes non-infringing, or remove the product or part and refund the purchase price (less reasonable depreciation for any period of use) provided that any transportation costs are separately paid by Buyer. The foregoing states the entire liability of Flow for patent infringement by using said products or any parts thereof.

c. The preceding paragraph shall not apply to (i) any Equipment that is modified, customized or manufactured to Buyer's design or specifications, or (ii) the use of any Equipment furnished to Buyer in combination with other products not furnished by Flow, unless the Equipment, per se, infringes the asserted patent. As to any such excluded product or part thereof, Flow assumes no liability whatsoever for patent infringement and Buyer shall hold Flow harmless against any infringement claims arising therefrom.

2. LIMITATION OF WARRANTIES

EXCEPT AS PROVIDED IN SECTION 1 ABOVE, FLOW MAKES NO OTHER WARRANTIES TO BUYER, EXPRESS OR IMPLIED, AND HEREBY EXPRESSLY DISCLAIMS ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

3. ACCEPTANCE, DELIVERY, TITLE AND RISK OF LOSS

Unless otherwise specified by Flow, delivery will be made and title will pass F.O.B. point of shipment to Buyer skidded for domestic truck shipment. Risk of loss or damage passes to Buyer on delivery.

Any export or other special packing or special transportation charges shall be charged to and paid by Buyer. Except as otherwise agreed to by Flow, Flow shall not be responsible for freight transportation, insurance, shipping, storage, handling demurrage, or similar charges (including duties, taxes, VAT, etc.). If such charges are by the terms of sale included in the price, any increase in rates becoming effective after the date hereof shall be for the account of and responsibility of Buyer.

4. TIME NOT OF THE ESSENCE UNLESS EXPRESSLY PROVIDED

Time is not of the essence with respect to any times or dates included in the Agreement unless the Agreement expressly indicates that those times or dates are of the essence. Any dates for payments from or by Buyer to Flow are of the essence.

5. EXCUSABLE DELAYS

Flow shall not be liable for delays in delivery or performance, or for failure to manufacture, deliver or perform, for reasons including, but not limited to, (i) a cause beyond its reasonable control, or (ii) an act of God, act of Buyer, act of civil or military authority, Governmental priority, strike or other labor disturbance, flood, epidemic, war, riot, delay in transportation, or (iii) inability on account of a cause beyond the reasonable control of Flow to obtain necessary materials, components, services or facilities. Flow will notify Buyer of any material delay excused by this section and will specify the revised delivery date, as soon as practicable. Any such delay shall not give rise to any termination right and the date of such delivery or performance shall be extended for a period equal to the time lost by reason of delay.

6. BUYER'S CREDIT

Flow may request advance payments or adequate security for deliveries required by the Agreement, including Equipment already delivered. Flow reserves the absolute right, among other remedies, to terminate this Agreement or to suspend further performance under this Agreement in the event Buyer fails to provide such payments or security within 20 days of Flow's request. Upon such termination or suspension, Flow shall be entitled, upon demand, to be indemnified for and against all costs and expenses already incurred or commitments made by Flow in or towards its performance under this Agreement.

7. DISCLOSURE OF INFORMATION

Any information, suggestions or ideas transmitted by Buyer to Flow in connection with performance under this Agreement are not to be regarded as secret or confidential except as may be otherwise provided by agreement in writing signed by a duly authorized representative of Flow.

8. TAXES

In addition to any price specified in the Agreement, Buyer shall bear, pay and be responsible for the gross amount of any present or future taxes, duties or levies, of a sales, use, excise, value added, goods and services or other similar nature, applicable to or assessable on the price, sale or delivery of any products or services furnished under the Agreement or to their use by Flow or Buyer or otherwise applicable to the transactions under the Agreement, or Buyer shall furnish Flow with evidence of exemption acceptable to the taxing authorities.

9. LIMITATIONS OF DAMAGES

FLOW SHALL NOT BE LIABLE FOR INCIDENTAL OR CONSEQUENTIAL DAMAGES INCLUDING, BUT NOT LIMITED TO, LOSS OF PROFITS, LOSS OF USE, LOSS OF PRODUCTION, DAMAGE TO OTHER EQUIPMENT, COST OF CAPITAL OR INTEREST. FLOW'S LIABILITY IS LIMITED TO REPAIR OR REPLACEMENT OF THE EQUIPMENT AND THE DETERMINATION REGARDING WHICH OF THESE IS APPROPRIATE SHALL BE AT FLOW'S SOLE DISCRETION. THE PARTIES AGREE THAT THE FOREGOING REMEDY IS REASONABLE AND DOES NOT CAUSE THE AGREEMENT TO FAIL IN ITS ESSENTIAL PURPOSE.

10. CANCELLATION

The Buyer does not have the right to cancel this Agreement or any portion of this Agreement unless the Buyer's request for cancellation is approved in writing by an authorized representative of Flow. If Flow so approves the cancellation of this Agreement or any portion of this Agreement, Buyer acknowledges that Flow will be damaged by the cancellation and that the damages sustained by Flow will be difficult to calculate. Therefore, Flow is entitled to recover from Buyer the immediate payment of liquidated damages calculated as follows: (a) in respect of Standard/Non-Customized Equipment and Spare Parts and Consumables: an amount equal to (i) all costs and expenses incurred by Flow in its performance of the Agreement up to the date of approved cancellation, (ii) plus an amount equal to all commitments for or towards the purchase of goods, materials and services made by Flow in connection with the processing, handling and fabrication of the Equipment, (iii) plus the payment to Flow of 10% of the total sale price, which Buyer acknowledges represents a reasonable amount for Flow's overhead and profit; or (b) in respect of Custom Equipment: at Flow's option (i) an amount equal to the revenue recognized by Flow for the Equipment on a percentage of completion basis or (ii) the amount determined pursuant to (a) above with respect to Standard/Non-Customized Equipment. Any progress payments already made prior to such cancellation shall be applied towards the total amount determined according to the foregoing sentence.

11. INSTALLATION & TRAINING

Unless otherwise agreed by Flow in writing, installation and training services are not included in the sale price except as specified; however, such services, including travel time and overtime premium charges, will be provided if requested at Flow's quoted service rate as may be applicable for working hours.

12. INTELLECTUAL PROPERTY

The Equipment and its documentation have been developed by Flow and represent a significant investment in industrial and intellectual property. No ownership of any patent, copyright, trade secret, technical data or other industrial or intellectual property is transferred to Buyer hereunder. No Equipment sale is to be construed as the grant by Flow to the Buyer of any license to copy, modify, revise or reconstruct anything falling within the scope of patents, copyrights, trade secrets, technical data, or other industrial property of Flow or third parties.

13. INDEMNIFICATION

Buyer shall indemnify and hold Flow harmless from and against any and all losses, claims, costs, expenses, damages and liabilities, including reasonable attorney's fees, which Flow may suffer or be required to pay, arising out of injury (or death) to persons, or damage to property, resulting from or pertaining to the negligent use or operation of the Equipment whether or not occasioned by the negligence of Buyer, employees, independent contractors or invitees.

14. ENFORCEMENT

a. **Validity, interpretation and performance.** The validity, interpretation and performance of the Agreement shall be governed by the laws of the State of Washington in effect at the time of contracting. Ambiguities will not be construed against the drafter. Flow may bring an action to enforce the Agreement in state and federal courts located in the jurisdiction of the Buyer, or any other jurisdiction the venue rules of which would allow maintenance of such an action.

b. **Default.** Buyer shall be in default of this Agreement in any of the following circumstances: (i) a failure to make any payment due within 10 days of the date on which that payment is due; (ii) a failure to perform or satisfy any covenant, condition or warranty of this agreement, other than payment, where such failure continues for 10 days after Buyer is given notice of such failure; (iii) Buyer's default under any note, security agreement, equipment lease or similar document evidencing indebtedness between Buyer and either Flow or a third party where such default permits the holder of such indebtedness to cause such indebtedness to become due before its stated maturity; (iv) any representation or warranty made by Buyer shall prove to be materially incorrect or the conditions of Buyer's business affairs shall change so as in the opinion of Flow to materially impair Flow's interest or increase materially Flow's credit risk; (v) Buyer shall generally not pay its debts as they come due, file or have filed against it a petition under any bankruptcy or insolvency law, make an assignment for the benefit of its creditors, consent to the appointment of a custodian, receiver; trustee or other officer with similar powers, be adjudicated insolvent or be liquidated; (vi) Buyer or any guarantor of Buyer is declared legally deceased (if Buyer is a sole proprietor or general partner) or if Buyer shall terminate its existence by merger, consolidation, sale of substantially all of its assets or otherwise; or (vii) Buyer shall agree with any third party to any lien or encumbrance that will in any way affect Flow's ability to obtain any of the remedies provided for in this Agreement.

c. **Remedies.** Upon default by Buyer, Flow may exercise any or all of the following remedies with respect to the Equipment: (i) replevin, repossession or seizure, by judicial process or otherwise; (ii) acceleration of remaining payments so that they are immediately due; (iii) damages for any unpaid portions of the sales price, loss or for consequential or incidental damages and (iv) attorneys' fees and costs of litigation. This list of remedies is not exclusive or exhaustive. Each of these remedies shall be cumulative and in addition to any other remedies available under this Agreement, at law or in equity. In the event any amount due under this Agreement is not timely paid, Flow shall be entitled, in addition to any other remedy, to (i) a finance charge of 1½% per month (18% per year) for such overdue amounts and (ii) all reasonable collection costs, including legal fees. This finance charge shall also apply to any suspension, termination or cancellation as provided in these terms and conditions.

15. GENERAL TERMS

a. **Flow's Terms Control.** ANY ACCEPTANCE OF THE BUYER, INCLUDING ANY PURCHASE ORDERS, MUST BE MADE ON THESE EXACT TERMS UNLESS FLOW EXPRESSLY AGREES TO ANY ADDITIONAL OR DIFFERENT TERMS. TO THE EXTENT THESE TERMS ARE CONSTRUED AS AN ACCEPTANCE OF AN OFFER MADE BY BUYER, THE ACCEPTANCE IS EXPRESSLY MADE CONDITIONAL ON BUYER'S ASSENT TO ANY TERMS AND CONDITIONS IN THIS TERMS. FOR PURPOSES OF CLARIFICATION, ANY TERMS INCLUDED IN ANY BUYER-DRAFTED DOCUMENT (E.G. BUYERREVISED QUOTATION, PURCHASE ORDER) DO NOT FORM PART OF THE AGREEMENT BETWEEN FLOW AND THE BUYER UNLESS FLOW EXPRESSLY AGREES TO ANY SUCH ADDITIONAL OR DIFFERENT TERMS.

b. **Entire Agreement.** The Agreement constitutes the entire agreement of the parties, and they supersede all prior written or oral representations made by the parties with respect to the subjects addressed in this Agreement.

c. **Amendments.** No purported modification or variance of the Agreement will be effective or enforceable unless made in writing and signed by an authorized representative of the party against whom enforcement of such a purported modification or variance is sought. For there to be a valid agreement by Flow, there must be a document manifesting that agreement and signed by an authorized representative of Flow. Flow will not be deemed to have entered into a contract as a result of its conduct, and Flow shall not be bound by any purported oral agreements, whether by operation of law or otherwise.

d. **Industry Custom, Usage of Trade or Course of Performance.** The parties do not intend that the express terms of the Agreement will be modified, varied or supplemented by industry custom, usage of trade or course of performance unless the other documents (where applicable) comprised in the Agreement expressly incorporate such industry custom, usage of trade or course of performance.

e. **Conflict Among Flow's Terms.** In the event of a conflict or any ambiguities between these terms and conditions and any terms and conditions contained in a quotation, order acknowledgement, or other Flow-issued documents (for conflict between Flow's terms and Buyer's terms, see Section 15(a) above), the following order of priority shall apply: (i) terms on the order acknowledgment (if any), (ii) terms on the quotation, (iii) these terms and conditions.

f. **Waiver.** The failure of Flow to object to any provision in conflict with the Agreement shall not be construed as a waiver of any of this Agreement, and the failure of Flow to enforce any of the provisions of this Agreement shall not be construed in any sense as a waiver.

g. **Third Party Beneficiaries.** The parties do not intend that the Agreement shall create a right of enforcement by any third party and the parties expressly intend that there be no third parties with standing to enforce any provision of the parties' Agreement. In the event Buyer obtains funding from a third party or Flow enters into any agreement with such financier, Buyer agrees that Buyer shall have no rights as a third-party beneficiary in any contract between Flow and that third party.

h. **Liens.** The Buyer shall not allow the Equipment to become subject to any lien or encumbrance, including but not limited to a mechanic's lien, without the express, written permission of Flow. If the Buyer violates this provision, it shall be responsible immediately to take all steps necessary to remove or satisfy any such lien and to pay all reasonable legal fees and costs incurred by Flow as a result of the imposition of such a lien.

i. **Severability.** Any determination that a provision of this Agreement is unenforceable will not affect the enforceability of the remaining provisions of this Agreement.

STANDARD PAYMENT PROCESSING

STANDARD CASH TERMS:	▪ Deposit of 30% of total contract amount is required with submission of purchase order or signed quotation. Please advise if invoice is necessary. ▪ The order will not be placed in the Flow International Corporation (FLOW) build schedule UNTIL receipt of this deposit ▪ Payment of the 60% progress payments must be received 7 days from shipment or prior to installation scheduling, whichever comes first
WELLS FARGO:	▪ A signed quotation or purchase order will be required to initiate order. However, order will be booked into build schedule upon receipt of written approval by Wells Fargo. ▪ System will only be shipped upon receipt of unconditional purchase order from Wells Fargo ▪ Generally, this occurs upon signing of Wells Fargo documents as verification of insurance coverage on system
BANK FUNDING:	▪ A letter will be required from an acceptable bank evidencing that funding is adequate to fully cover machine purchase amount ▪ Receipt of Certificate of Insurance by lender, if required ▪ Verification that loan documents have been executed and returned to bank
THIRD PARTY LEASE:	▪ Verification of credit approval from leasing company and execution of all loan documents ▪ Issuance of purchase order to Flow by leasing company. Order can be entered into build plan at this stage ▪ Verification to Flow Credit group by leasing company that insurance coverage for machine is in place PRIOR to shipment

CREDIT APPLICATION

Please fax completed form to 253.813.3283. By completing this application you will help us to expedite the preliminary approval process required to become a credit customer. The completed application form is reviewed by our credit department and is held in strict confidence in accordance with our corporate confidentiality regulations.

General Information

Company name:		Federal ID number:	
Billing Address:			
City:		State:	Zip code:
Tel:	Fax:	URL:	
Shipping Address (if different than billing adress):			
City:		State:	Zip code:
Tel:	Fax:	URL:	
Type of business:		Years in business:	
Legal formation of company:		☐ Corporation ☐ Partnership ☐ Proprietorship	
Section A: Please fill out the fields listed below if you will be purchasing parts or service for your existing Flow equipment. This section not applicable for new equipment purchases.			
Equipment/Model:		Serial number:	
Purchased from:			
Additional information (if applicable):			
Section B: For your convenience, Flow accepts credit cards. Please fill out the fields listed below if you will be using a credit card to purchase parts, service, or equipment.			
Type of card:		☐ Visa® ☐ MasterCard® ☐ American Express®	
Please provide cardholder and account number information at time of order placement.			



SHAPE TECHNOLOGIES GROUP®

Michael Addesso Marble & Granite World

Q-13287-4

March 12, 2024

27/27

Credit References

Please provide three (3) credit references that Flow may contact.

Company name:	Contact name:	
Address:		
City:	State:	Zip code:
Tel:	Fax:	E-mail:
Company name:	Contact name:	
Address:		
City:	State:	Zip code:
Tel:	Fax:	E-mail:
Company name:	Contact name:	
Address:		
City:	State:	Zip code:
Tel:	Fax:	E-mail:

Bank Reference

Please provide one (1) bank reference that Flow may contact.

Bank name:	Account number:	
Address:		
City:	State:	Zip code:
Tel:	Fax:	E-mail:

Authorization

By submitting this application, you authorize Flow International Corporation to make inquiries into the credit and banking references you have supplied.

Authorized contact:	
Title:	Date:

Approval (internal use only)

Credit approval:	
Credit level approved:	Date: